

5/8" TYPE-X DRYWALL AT ALL EXTERIOR WALLS, TYP.

PARTIALLY-CONSTRUCTED 2-HR ACOUSTIC DEMISING WALLS, APPLY REMAINING GYPSUM BOARD & FIRE SEALANT, REFER PARTITION SCHEDULE, TYP.

FIRE EXTINGUISHER

FREE-STANDING DISPLAY SHELVES, BY TENANT

RETAIL DISPLAY 01

THE FIND 200-A

OUTLET CENTERED @ 43" AFF (WITHIN WALL TILE)

ALOE 200-C

wrapping supply wall

PROVIDE COLD WATER SUPPLY & DRAIN LINE CONNECTIONS FOR P.O.U. FREESTANDING COOLER (COOLER PROVIDED BY TENANT)

EXTEND WASTE LINE TO NEW PLUMBING FIXTURES & CONNECT TO EXISTING HOT/COLD WATER LINES AS REQ'D BY CODE

EXTEND NEW CODE-COMPLIANT HOT / COLD WATER LINE TO PLUMBING FIXTURES AS SCHEDULED, VENT TO ROOF AS REQ'D

BLDG SERVICE 200

200-B ELEC PANEL, TIE TO NEW SUBMETER

WALL SHELVES, BY TENANT

EXISTING WASTE LINE

BACK OF HOUSE 03


SPLIT SYSTEM OUTDOOR UNIT AS SPECIFIED BY CONTRACTOR, PROVIDE ADEQUATE CLEARANCE TO ADJACENT UNIT

M-1A

200-A OUTDOOR UNIT

EXISTING SLAB BLOCK-OUT; INSTALL STEEL & INFILL 3000 PSI CONCRETE AS REQ'D BY SHELL STRUCTURAL DRAWINGS AFTER PLUMBING INSTALLATION, REF S101 (ISSUE 09.30.2015), TYP.

200-C OUTDOOR UNIT



# 01 Floor Plan

SCALE: 1/4" = 1'-0"